BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

NAME OF WORK:- Maintenance of graveyard in ward no. 06

Sl. No.	Quantity.	Description	Unit	Rates	
1	18.00	KSRB 2-2.1:: Earthwork excavation for foundationof buildings, water supply and sanitary lines and electrical conduitsetc, either in pits or in trenches 1.5m and above in width, in soil notexceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications.. No. KBS 2.1(b) / 2.3.5 (pg no.6, I/No2.4,)	Cum	317.12	Rupees Three Hundred Seventeen and Paise Twelve Only
2	3.60	KSRB 4-1.2 : Providing and laying in position plain cement concreteof Mix 1:4:8 with OPC @ 220kgs, with 40mm and down size gradedgranite metal coarse aggregates @0.892cum and fine aggregates @0.465cum machine mixed, machine mixed, concrete laid in layers notexceeding 15 cms. thick, well compacted, in foundation, including costof all materials, labour, HOM curing complete as per specifications.Specification No. KBS 4.1, 4.2 (pg No.13.I.No.4.2)	Cum	5609.52	Rupees Five Thousand Six Hundred Nine and Paise Fifty Two Only
3	13.50	KSRB 5.2-3 : - Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones at 2m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 (P.No.25- I.No.5.6)	Cum	4963.68	Rupees Four Thousand Nine Hundred Sixty Three and Paise Sixty Eight Only
4	24.00	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth cills and string courses cost of all materials, labour complete as per specifications. No. KBS 4.6.2 (P.No.16 - I.No.4.31)	Sqm	386.64	Rupees Three Hundred Eighty Six and Paise Sixty Four Only

5	3.60	KSRB 4.2.1 : Providing and laying in position reinforced cement concrete of Design Mix M25 with OPC @ 340kgs, with 20mm and down size graded granite metal coarse aggregates @0.70 cum and fine aggregtes @ 0.47cum, with super plasticisers @ 3 liters confirming to IS 9103-1999 reafirmed-2008 at machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedastals, retaining walls, return walls, walls (any thickness) including attached pilasters,columns, pillars,posts,struts,buttresses,bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM curing, complete but excluding cost of reinforcement as per specifications.(P.No.14- I.No.4.10)	Cum	6276.96	Rupees Six Thousand Two Hundred Seventy Six and Paise Ninety Six Only
6	0.40	KSRB M2200-6 Providing T.M.T bars Fe 550 steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. MORTH Specification NO.1600&2200 (Pg No.229 Item No.28.8.3)	tonne	74316.96	Rupees Seventy Four Thousand Three Hundred Sixteen and Paise Ninety Six Only
7	72.00	KSRB 5-14: Providing and constructing load bearing wall with solid concrete blocks having block density not less than 1800kg/m3 having a minimum average compressive strength of 4.00 N/mm2 confirming to IS 2185 (Part 1):2005 and constructed with CM 1:4, as per IS 2572:2005 including cost of all materials labour charges, scaffolding, curing, hire charges of machineries etc., complete as per specifications. blocks of size 400x1500x200mm KBS No.5.4 (P.No-27,I No-5.26.1)	Sqm	953.00	Rupees Nine Hundred Fifty Three Only

"DTS APPROVED"

ಮುಖ್ಯ ಅಭಿಯಂತರರು
ಯಲಹಂಕ ವಲಯ
ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ

01/12

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

01/12